



State of Utah

Jon M. Huntsman, Jr.
Governor

Gary R. Herbert
Lieutenant Governor

Utah Department of Public Safety
Scott T. Duncan
Commissioner

Final Fire Safety Inspection Self-Check Guide

The following list is intended to help provide you with an idea of the items that will be evaluated during a final inspection for a Fire Safety Clearance Certificate. ***This is NOT a comprehensive list.*** We recommend that you contact the Deputy State Fire Marshal in your area for specific requirements based on the type of construction and occupancy type.

Fire Sprinklers System:

- Main Drain Test: To record the static and residual pressures available at the sprinkler riser.
- Inspector's Test: To evaluate the time delay for activation of the fire alarm system and verify the activation of the water motor gong or electric bell upon water flow
- Test the tamper switches on the riser
- Evaluate the sprinkler head coverage throughout building
- Provide documentation of the "Underground" test, the "Above ground" test and materials certificates
- Verify that there is a box with the correct number and type of spare sprinkler heads and a wrench available.
- Verify that the FDC Cap(s) are in place
- Verify that the hydraulic calculation sticker is attached to the system riser and that the main drain test values fall within the hydraulic calculations of the system.
- Verify that the Main Drain and Inspector test valves are labeled

Electrical:

- Verify that all electrical panels are labeled and have no open spaces
- Verify the emergency lighting coverage throughout areas of egress and areas of assembly over 50
- Verify generator operation within 10 seconds of power failure if required
- Verify smoke detector placement *{NO detectors within 3 feet of any HVAC diffuser}*
- Verify that magnetic hold open devices allow doors to close on alarm activation
- Verify that magnetic locking or security devices fail open on alarm or loss of power

Fire Alarm Panel:

- Conduct a 24-hour battery test *{Power to the fire alarm panel MUST be disconnected 24 hours prior to this test unless otherwise indicated}* Test requires that batteries are able to carry the full current load of the alarm system for at least 5 minutes after being disconnected from power for 24 hours.
- Test all horn/strobe units and pull stations
- Test for open circuit and ground fault problems within the system
- Verify that devices are labeled and that a map of devices is posted at the alarm panel
- Verify that a monitoring company monitors the alarm system if required

HVAC:

- Verify that systems over 2,000 CFM have air return duct detectors and shutdown on alarm activation
- Verify operation of all fire and smoke dampers including access panels to these devices

General:

- Verify that all exits provide egress to a public way
- Inspect and verify function of kitchen hood extinguishing systems
- Verify fire extinguisher coverage including a type "K" extinguisher in commercial kitchens where required
- Verify location and operation of exit signs
- You should also have your approved plans onsite for review

Ron L. Morris, State Fire Marshal

5272 South College Drive Suite 302, Murray Utah 84123-2611
Telephone 801-284-6350 – Facsimile 801-284-6351 – Web Site <http://firemarshal.utah.gov/>